FIRST ARTICLE TEST REQUIREMENTS (GOVERNMENT TESTING)

P/N: (78286) 70400-01612-044
NOMEN: BALL BEARING UNIT
NSN: 3130-01-383-7605

I. First Article Inspection/Test Criteria:

The tests to be performed under the First Article approval clause of the contract are:

A. Compliance with **Sikorsky Drawing (78286) 70400-01612, Rev. D or latest revision** and all specifications referenced therein.

B. Identification: Verification and certification that the parts are serialized and identified per the requirements of **Sikorsky Drawing (78286) 70400-01612, Rev. D or latest revision** and all specifications referenced therein.

C. Packaging and Preservation: Verification that the parts have been packaged and preserved per the requirements of the contract.

D. Verification and certification of the overall workmanship of the First Article Sample(s).

E. Dimensional: 100% dimensional.

F. Non-Destructive Inspection: Verification and certification of Fluorescent Penetrant Inspection per MIL-I-6866.

G. Fit/Form: Verification and certification of fit/form to the next higher assembly, H60 P/N (78286) 70400-21600-012.

H. Material Analysis of the First Article Sample(s):

1) Destructive material analysis to verify material composition of Sub-Assembly, P/N 70400-01612-101, 7075-T7351.

2) Destructive material analysis to verify material composition of Sub-Assembly, P/N 70400-01612-104, AMS-R-6855, CL 2 GR 60.

3) Verification of compliance with anodize per MIL-A-8625.

I. Review of documentation as provided under DD 1423 requirements.

FIRST ARTICLE TESTS REQUIREMENTS (GOVERNMENT TESTING) continued

In addition to the above tests, the First Article(s) to be delivered hereunder shall also be subjected to those tests, which will demonstrate that the articles comply with contract requirements. The contractor shall be responsible for providing necessary parts and repair of the First Article(s) during testing.

II. Samples to be submitted for testing:

A. Quantity 2 each.

B. Estimated Cost: T.B.D.

III. Special Instructions:

A. Upon successful first article inspection all processes are to be frozen. Any changes to the manufacturing process will be cause for a new First Article Inspection.

B. One sample will be destroyed during testing and will not be returned to the contractor. One sample may be considered as production items under the contract provided the sample could be refurbished to ready for issue (RFI) condition and provided the sample has inspection approval of the cognizant QAR. Sample(s) may be shipped as production items only after all other units required under the contract have been produced and are ready for shipment.

C. Waiver of the destruction of the First Article test piece may be granted if the contractor provides a certified test coupon that is of the same material and has undergone the same special processes as the First Article test piece.

D. One sample is to be unpainted and all corrosive areas are to be coated with a light preservative on both samples.

Notification of Shipment of Material for Government Testing

A. Fourteen (14) days prior to shipment of the First Article Sample(s) the contractor shall notify the designated test facility, in writing of the anticipated shipping date, with an information copy to the PCO, ACO, and QAR. The contractor shall also arrange for preliminary inspection of test sample(s) by the CAO/QAR. The First Article Sample(s) shall be forwarded to the following First Article point of contact at the designated test facility:

Commanding Officer
Naval Air Depot
Attn: Code 3.3.2 (Mr. Steve Lundberg)
Bldg. 159, Door R-4
Cherry Point, NC 28533-0021

FIRST ARTICLE TESTS REQUIREMENTS (GOVERNMENT TESTING) continued

B. Upon shipment of First Article Sample(s), two (2) copies of the Material Inspection and Receiving Report (DD Form 250), bearing the QAR's signature and indication of preliminary inspection, shall be forwarded to the PCO/ACO DSCR Code DSCR-VC, and the designated test facility. In addition, the contractor must supply all detailed process/operation sheets, Inspection Method Sheets, First Article Test Report (Signed by the QAR), and all Certificates of Compliance for material (including chemical analysis), **Fluorescent Penetrant Inspection** and any out-sourced process conducted on the First Article Sample(s). These forms and documentation may either be placed in the shipping container with the sample(s) or sent separately, however the envelopes shall be clearly marked, "DO NOT OPEN IN MAILROOM." These forms and documentation shall be sent to the following point of contact:

Commanding Officer
Naval Air Depot
Attn: Code 3.3.2 (Mr. Steve Lundberg)
Bldg. 159, Door R-4
Cherry Point, NC 28533-0021

Within 120 days after receipt of the sample(s) the test site shall complete testing/evaluation and submit a copy of their test report with conclusions and recommendations to DSCR-VC.

MANDATORY QUALITY ASSURANCE PROVISIONS

P/N: **(78286) 70400-01612-044**
NOMEN: **BALL BEARING UNIT**
NSN: **3130-01-383-7605**

APPLICABLE CLAUSES:

Articles to be furnished hereunder shall be manufactured, tested and inspected in accordance with drawing number **(78286) 70400-01612, Revision "D" or latest revision** and all details and specifications referenced therein.

I. Process/Operation Sheets Revision "**D" or latest revision** date shall be utilized in manufacture of the articles to be furnished hereunder.

II. Quality/Inspection Requirements

A. MIL-I-45208 applies or ISO 9000 equivalent.

B. MIL-Q-9858 applies or ISO 9000 equivalent.

C. First Article testing applies. (Government Testing)

D. Production Lot Testing applies. (Government Testing)

E. Site Survey required prior to contract award.

III. Supplemental Requirements

A. Additionally, paragraphs 3.1-3.5, 5.1-5.2, and 6.1-6.2 of MIL-Q-9858 apply or ISO 9000 equivalent applies.

B. The contractor shall identify on the process/operation sheets, a tracking method that is traceable to the contract, and all manufacturing sources performing processes/operations outside of their facilities. These sheets shall not be revised or altered after the successful completion of First Article or Production Lot Testing without approval from the ESA located at the Naval Air Depot, Cherry Point, North Carolina, via the PCO.

C. The Inspection Method Sheets, which list the characteristics of each item produced under the contract shall have serial number traceability to the raw material, casting, or forging. The tracking method used on the inspection/method sheets shall be traceable to the contract. In addition, the contractor is responsible for providing completed inspection method sheets showing the actual dimensions taken of all critical characteristics.

MANDATORY QUALITY ASSURANCE PROVISIONS continued

D. The contractor shall provide all certificates of compliance for any material purchased or any processes performed by a sub-vendor, i.e. heat treat, NDI, plating, painting, etc. All material and/or process sub-vendors shall be OEM approved sources.

E. Markings should be I/A/W MIL-STD-130 latest revision, paragraphs 5.3.3(a), (b), (c) and (g). Method and location shall be I/A/W drawing.

IV. Mandatory Inspection Requirements

During production, mandatory inspection is required to be accomplished by the contractor as follows:

A. Level of Inspection (LOI).

1) Critical Characteristics: 100% inspection shall apply

2) Major and Minor Characteristics - LOI shall be I/A/W sampling plan acceptable to the QAR

B. Critical Characteristics **Sikorsky Drawing (78286) 70400-01612**:

1) Diameter 2.2494" to 2.2489"

2) Diameter .264" to .262"

3) Material Analysis of Sub-Assembly, Support, P/N 70400-01612-101: 7075-T7351

4) Material Analysis of Sub-Assembly, Boot, P/N 70400-01612-104: AMS –R-6855, CL 2 GR 60

5) Verify and certify Bearing rotation 8 inch oz. Max. drag at room temperature.

6) Non-Destructive: Fluorescent Penetrant inspect Per MIL-I-6866

C. Major and Minor Characteristics

1) Shall be defined by the contractor subject to QAR concurrence, unless defined on applicable drawings and associated specifications.

PRODUCTION LOT TESTING REQUIREMENTS (GOVERNMENT TESTING)

P/N: (78286) 70400-01612-044
NOMEN: BALL BEARING UNIT
NSN: 3130-01-383-7605
QUANTITY: 2

The material produced under contract shall be accepted by the cognizant CAO/QAR upon the successful completion of these requirements.

I. Production Lot Test Requirements

A. The cognizant CAO/QAR shall select the applicable number of items at random from the production lot per the ANSI/ASQC Z1-4 Sampling Procedures and Tables for Inspection by Attributes. In addition the QAR shall select the applicable number of items at random from each successive lot or portion thereof per the ANSI/ASQC Z1-4 Sampling Procedures and Tables for Inspection by Attributes.

B. Production Lot Testing to be completed during production after First Article Approval.

C. Sample(s) are to be unpainted. Corrosive areas to be coated with a light preservative.

D. If sample(s) are not destroyed during testing, they will be put into Defense Logistic Agency stock.

II. The tests to be performed under the Production Lot Sample testing provisions of the contract are:

A. Compliance with **Sikorsky Drawing (78286) 70400-01612, Rev. D or latest revision** and all details and specifications referenced therein.

B. Identification: Verification and certification that the parts are serialized and identified per the requirements of **Sikorsky Drawing (78286) 70400-01612, Rev. D or latest revision** and all details and specifications referenced therein.

C. Packaging and Preservation: Verification that the parts have been packaged and preserved per the requirements of the contract.

D. **Visual: Verification and certification of the overall workmanship of the Production Lot Sample(s).**

E. Dimensional: Verification and certification of 100% dimension check of finished Production Lot Sample(s).

F. Non-Destructive Inspection: Verification and certification of Fluorescent Penetrant Inspection per MIL-I-6866.

PRODUCTION LOT TESTING REQUIREMENTS (GOVERNMENT TESTING)

G. Fit/Form/Function: Verification and certification of fit/form/function to the next higher assembly, **H60 P/N (78286) 70400-21600-012.**

H. Material Analysis of the Production Lot Sample(s). NOTE: A destructive material analysis can be waived **ONLY** if a destructive material analysis was conducted by the Engineering Support Activity (ESA), **AIR-4.3.4.1, Naval Air Depot, Cherry Point, NC** during a successful First Article Inspection. However, all applicable material certificates of compliance will have to be provided for the production lot for verification of the material.

1) Destructive material analysis to verify material composition of Sub-Assembly P/N P/N 70400-01612-101, 7075-T7351.

2) Destructive material analysis to verify material composition of Sub-Assembly P/N P/N 70400-01612-104, AMS-R-6855, CL 2 GR 60.

3) Verification of compliance with anodize per MIL-A-8625.

I. Review of documentation as provided under DD 1423 requirements.

In addition to the above tests, the Product Lot Sample(s) to be delivered hereunder shall also be subjected to those tests that will demonstrate that the sample(s) comply with contract requirements.

III. Testing Location

A. The contractor is to ship sample(s) and all required documentation and technical data to:

Commanding Officer
Naval Air Depot
Attn: Code 3.3.2 (Mr. Steve Lundberg)
PSC Box 8021
Cherry Point, NC 28533-0021

B. The shipping container marking: "FOR PRODUCTION LOT TESTING. NON RFI MATERIAL. DO NOT TAKE UP IN STOCK. CONTRACT NUMBER_____. "

Within fifteen (15) days of completion of Production Lot Testing the CAO/QAR shall prepare and submit two (2) copies of their test report with conclusions and recommendations to the Contracting Officer.

Shipment and Distribution of Sample(s):

A. Fourteen (14) days prior to shipment of Production Lot Sample(s) the contractor shall notify the designated test facility, in writing of the anticipated shipping date, with an information copy to the PCO, ACO and the QAR. The contractor shall also arrange for preliminary inspection of test samples by the CAO/QAR.

B. Upon shipment of the Production Lot Sample(s), two (2) copies of the Material Inspection and Receiving Report (DD Form 250), bearing the QAR's signature and indication of preliminary inspection, shall be forwarded to the PCO/ACO **DSCR (Code DSCR-VC),** and the testing facility. In addition, the contractor shall provide all detailed Process/Operation Sheets, Inspection Method Sheets, First Article Test Report (Signed by the QAR), and all Certificates of Compliance for material (including chemical analysis), **Fluorescent Penetrant** Inspection, any out-sourced process conducted on the Production Lot Sample(s) and all technical data used to manufacture the Production Lot Sample(s) to the testing facility. The envelopes shall be clearly marked, "DO NOT OPEN IN MAILROOM".

C. Production Lot Sample(s) may be considered as production items under the contract provided the sample(s) can be refurbished to Ready for Issue (RFI) condition and provided sample(s) have inspection approval from the cognizant DCMAO and the ESA engineer (**MMHISST.1 (AIR-4.3.3)).** Sample(s) may be shipped as production items **ONLY** after all other units required under contract have been produced and are ready for shipment.

D. Sample(s) will be returned to the contractor. The contractor must provide material disposition instructions to:

Commanding Officer
Naval Air Depot
Attn: Code 3.3.2 (Mr. Steve Lundberg)
PSC Box 8021
Cherry Point, NC 28533-0021

E. The designated test facility and the contracting officer shall be notified as to all shipping data applicable to the sample(s), such as bill of lading number, method of shipment, etc. within fourteen (14) days prior to shipping.

PRODUCTION LOT TESTING APPROVAL (GOVERNMENT TESTING)

NSN: 3130-01-383-7605
P/N: (78286) 70400-01612-044
NOMENCLATURE: BALL BEARING UNIT

A. The Production Lot Samples shall be:

1. Selected at random by the cognizant government QAR. Such samples shall be submitted via the cognizant government inspector, and all transportation charges prepaid by the contractor to:

Commanding Officer
Naval Air Depot
Attn: Code 3.3.2 (Mr. Steve Lundberg)
PSC Box 8021
Cherry Point, NC 28533-0021

2. The samples shipping container and samples shall be identified by contract number, lot number and be clearly marked as follows:

PRODUCTION LOT TEST SAMPLES
NON-RFI MATERIAL
DO NOT TAKE UP IN STOCK

B. Such samples shall be delivered to the testing facility in sufficient time prior to the delivery date of the production articles to allow a 90 day period for testing and written notification by the contracting officer of the approval or disapproval of the samples. Within 120 days of the receipt of the samples, the testing facility shall notify the contracting officer, PCO/ACO of the results of the testing, together with the recommendation for approval or disapproval.

C. In the event the contractor does not receive written notification of approval or disapproval of the samples for a particular lot within 120 days from their submission for such testing, the contract delivery schedule shall be equitably adjusted as necessary.

D. If the contractor fails to deliver any Production Lot Samples for testing within the time or times specified, or if the contracting officer disapproves any Production Lot Samples, the contractor shall be deemed to have failed to make delivery within the meaning of the default clause of this contract, and this contract shall be subject to termination for default.

E. In order for a Production Lot to be acceptable, all samples representative of the lot must pass all the contract requirements. In the event a sample fails to pass such requirements, the lot will be rejected. In such event, the government may, at its option and at no additional cost to the government, (I) terminated all or any portion of this contract for default, (II) require the manufacture of a new Production Lot, or a rework of the rejected Production Lot if the means and procedures by the contractor for rework are acceptable to the government, or (III) require the

submission of additional samples for test. The foregoing procedures shall apply to new or reworked Production Lots in the same way as they did to the original Production Lot.

F. For each additional sample or each resubmission of a modified sample which the contractor is required to submit for approval hereunder as a result of a failure of a previous sample to conform to the requirements of the specification, the contractor shall pay to the government the costs of reinspection, examination and retesting and the contractor and his sureties (if any) shall be liable for the amount of such costs.

G. The contractor must provide material disposition instructions to the First Article Coordinator at the **Naval Air Depot, Cherry Point, NC (Mr. Steve Lundberg, Code 3.3.2)** for the return of the production lot samples.

H. Nothing contained in the foregoing provisions of this clause, and not action of the government in accordance herewith, shall in any way prejudice the right of the government under this clause of this contract entitled default.

FIRST ARTICLE APPROVAL (GOVERNMENT TESTING)

NSN: 3130-01-383-7605
P/N: **(78286) 70400-01612-044**
NOMENCLATURE: **BALL BEARING UNIT**
APPLICABLE CLAUSES:

A. The contractor shall deliver unit(s) of lot/item within 180 calendar days from the date of this contract to the activity listed below for the purpose of partial inspection/testing and preparation of test report per the requirements specified in MIL-HDBK-831 prior to forwarding sample(s) with report to the Government designated test facility listed below:

Commanding Officer
Naval Air Depot
Attn: Code 3.3.2 (Mr. Steve Lundberg)
PSC Box 8021
Cherry Point, NC 28533-0021

B. The contractor shall deliver 2 unit(s) of lot/item within 180 calendar days from the date of this contract to the Government Marking of test sample(s) shipping container: "FOR FIRST ARTICLE TESTING. NOT RFI MATERIAL. DO NOT TAKE UP IN STOCK. CONTRACT NUMBER: .....For First Article Test, the shipping documentation shall contain this contract number and the lot/item identification. The characteristics that the First Article must meet the testing requirements are specified elsewhere in this contract.

C. Within 120 calendar days after the Government testing facility receives the First Article Sample(s), the QAR's signed Material Inspection and Receiving Report, DD Form 250 and all detailed Process/Operation Sheets, Inspection Method Sheets, First Article Test Report (Signed by the QAR), and all Certificates of Compliance for material (including chemical analysis), **Fluorescent Penetrant** Inspection, any out-sourced process conducted on the First Article Sample(s) and all technical data used to manufacture the First Article Sample(s), the contracting officer shall notify the contractor, in writing, of the conditional approval, approval or disapproval of the First Article. The notice of conditional approval or approval shall not relieve the contractor from complying with all requirements of the specifications and all other terms and conditions of this contract. A notice of conditional approval shall state any further action required of the contractor. A notice of disapproval shall cite reasons for the disapproval.

D. If the First Article is disapproved, the contractor, upon Government request, shall submit an additional First Article for testing. After each request, the contractor shall make any necessary changes, modification, or repairs to the First Article or select another First Article for testing. All costs related to these tests are to be borne by the contractor, including any and all costs for additional tests following disapproval. The contractor shall furnish any additional First Article to the Government under the terms and conditions and within the time specified by the

Government. The Government shall act on this First Article within the time limit specified in paragraph B above. The Government reserves the right to require an equitable adjustment of the contract price for any extension of the delivery schedule or for any additional costs to the Government related to these tests.

E. If the contractor fails to deliver any First Article on time, or the contracting officer disapproves any First Article, the contractor shall be deemed to have failed to make delivery within the meaning of the default clause of this contract.

F. Unless otherwise provided in the contract, the contractor

1) May deliver the approved First Article as a part of the contract quantity, provided it meets all contract requirements for acceptance and was not consumed or destroyed in testing and;

2) Shall remove and dispose of any First Article from the Government test facility at the contractor's expense.

G. If the Government does not act within the time specified in paragraph B or C above, the contracting officer shall, upon timely written request from the contractor, equitably adjust under the changes clause of this contract the delivery or performance dates and/or the contract price, and any other contractual term affected by the delay.

H. The contractor is responsible for providing operating and maintenance instructions, spare parts support, and repair of the, First Article during any First Article Test.

I. Before First Article approval, the acquisition of materials or components for, or the commencement of production of, the balance of the contract quantity is at the sole risk of the contractor. Before First Article approval, the costs thereof shall not be allocable to this contract for

1) progress payments, or

2) termination settlements if the contract is terminated for the convenience of the Government.

J. The contractor shall produce both the First Article and the production quantity at the same facility and shall submit a certification to this effect with each First Article.

K. The contractor shall provide specific written notification to the procuring contracting officer informing him of the shipment of any; article(s) furnished in accordance with this clause. Such notification must be addressed to the attention of the ACO with copies to **DSCR-VC** and to the testing activity. Failure to provide such notification shall excuse the Government from any delay in performing First Article Testing and informing the contractor of the results thereof.

CONTRACT DATA REQUIREMENTS LIST

Form Approved
CMB No. 0704-0188

Public reporting burden for this collection of information is estimated to average 110 hours per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden to Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 222202-2302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503. Please DO NOT RETURN your form to either of these addresses. Send completed form to the Government Issuing Contracting Officer for the Contract. PR No. listed in Block E.

A. Contract Line Item No.	B. Exhibit	C. Category ENGINEERING

D. System/Item	E. Contract/PR NO	F. Contractor
3130-01-383-7605		

1. Data Item No.	2. Title of Data Item: CERTIFICATION/DATA REPORTS	3. Subtitle: BLOCK 16*
0005		

4. Authority (Data Acquisition Document No.)	5. Contract Reference	6. Requiring Office
DI-MISC-80678/T3		DSCR

7. DD 250 Req	9. Dist Statement Required	10. Frequency	12. Date of First Submission	14. Distribution
LT		AS REQUIRED	BLOCK 16*	
8. APP Code		11. As of Date	13. Date of Subsequent Submission	a. Addressee / b. Copies
A			BLOCK 16**	

16. REMARKS

PARA. 10.1, 10.2.1, 10.2.2, 10.2.4, 10.5 APPLY

BLOCK 3:

SEPARATE REPORTS SHALL BE PROVIDED FOR THE BELOW LISTED SUBTITLES AND SHALL INCLUDE CERTIFICATIONS THAT ALL VENDORS PERFORMING THESE PROCESSES ARE PRIME (OEM) APPROVED SOURCES. IN THE CASE WHERE OTHER THAN THE OEM'S SPECIFICATIONS ARE TO BE UTILIZED, SEPARATE CERTIFICATIONS ARE REQUIRED.

1. MATERIAL CERTIFICATIONS AND ANALYSIS DOCUMENTATION FOR:

a. Destructive material analysis to verify material composition of Sub-Assembly, P/N 70400-01612-101, 7075-T7351.

b. Destructive material analysis to verify material composition of Sub-Assembly, P/N 70400-01612-104, AMS-R-6855, CL 2 GR 60.

2. PROCESS CERTIFICATIONS FOR:

a. Verification of compliance with anodize per MIL-A-8625.

3. INSPECTION CERTIFICATIONS:

a. Verification and certification of Fluorescent Penetrant Inspection per MIL-I-6866.

BLOCK 12:

* UPON SUBMITTAL OF FIRST ARTICLE TESTING SAMPLE(S)

CONTRACTOR SITE: FOR REVIEW

GOVERNMENT SITE: AS DELIVERABLE

**UPON SUBMITTAL OF PRODUCTION LOT INSPECTION SAMPLE(S)

CONTRACTOR SITE: FOR REVIEW

GOVERNMENT SITE: AS DELIVERABLE

a. Addressee	b. Copies Draft	Final Reg	Final Repro
NAVAIR CP CODE 3.3.2		1	
DCMC/QAR		1	
DSCR/VC		1	
15. TOTAL		3	

G. PREPARED BY	H. DATE	I. APPROVED BY	J. DATE
Timothy L. Bennett *Timothy L Bennett*	19 August 03	*[signature]*	*10/10/03*

DD Form 1423-1, JUN 90 Previous editions are obsolete

CONTRACT DATA REQUIREMENTS LIST

Form Approved
OMB No. 0704-0188

The public reporting burden for this collection of information is estimated to average 440 hours per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing the burden, to Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports (0704-0188), 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number. Please DO NOT RETURN your form to the above address. Send completed form to the Government Issuing Contracting Officer for the Contract/PR No. listed in Block E.

A. CONTRACT LINE ITEM NO.	B. EXHIBIT	C. CATEGORY: TDP ____ TM ____ OTHER ____

D. SYSTEM/ITEM	E. CONTRACT/PR NO.	F. CONTRACTOR
3130-01-383-7605		

1. DATA ITEM NO. 0001
2. TITLE OF DATA ITEM CERTIFICATION DATA REPORTS
3. SUBTITLE DETAILED PROCESS/OPERATION SHEETS
17. PRICE GROUP
18. ESTIMATED TOTAL PRICE

4. AUTHORITY *(Data Acquisition Document No.)* DI-MISC-80678/T1
5. CONTRACT REFERENCE
6. REQUIRING OFFICE DEFENSE SUPPLY CENTER P

7. DD 250 REQ LT
8. APP CODE A
9. DIST STATEMENT REQUIRED
10. FREQUENCY AS REQUIRED
11. AS OF DATE
12. DATE OF FIRST SUBMISSION BLOCK 16*
13. DATE OF SUBSEQUENT SUBMISSION BLOCK 16*

14. DISTRIBUTION

a. ADDRESSEE	b. COPIES Draft	Final Reg	Final Repro
NAVAIR CP 3.3.2		1	
DSCR/VC		1	
CAO		1	
15. TOTAL →		3	

16. REMARKS
PARA. 10.1, 10.2, 10.2.1, 10.2.2, 10.2.4, 10.5 APPLY//*UPON SUBMISSION OF FIRST ARTICLE TESTING//**IF THE PROCESS/OPERATIONS CHANGES AFTER APPROVAL OF FIRST ARTICLE TEST

1. DATA ITEM NO. 0002
2. TITLE OF DATA ITEM CERTIFICATION DATA/ REPORT
3. SUBTITLE COMPLETE INSPECTION METHOD SHTS
17. PRICE GROUP
18. ESTIMATED TOTAL PRICE

4. AUTHORITY *(Data Acquisition Document No.)* DI-MISC-80678/T2
5. CONTRACT REFERENCE
6. REQUIRING OFFICE DEFENSE SUPPLY CENTER P

7. DD 250 REQ LT
8. APP CODE A
9. DIST STATEMENT REQUIRED
10. FREQUENCY AS REQUIRED
11. AS OF DATE
12. DATE OF FIRST SUBMISSION BLOCK 16*
13. DATE OF SUBSEQUENT SUBMISSION BLOCK 16*

14. DISTRIBUTION

a. ADDRESSEE	b. COPIES Draft	Final Reg	Final Repro
NAVAIR CP 3.3.2		1	
DSCR/VC		1	
CAO		1	
15. TOTAL →		3	

16. REMARKS
PARA. 10.1, 10.2, 10.2.1, 10.2.2, 10.2.4, 10.5 APPLY//*UPON SUBMISSION OF FIRST ARTICLE TESTING//**IF THE PROCESS/OPERATIONS CHANGES AFTER APPROVAL OF FIRST ARTICLE TEST

1. DATA ITEM NO. 0003
2. TITLE OF DATA ITEM REQUEST FOR DEVIATION
3. SUBTITLE
17. PRICE GROUP
18. ESTIMATED TOTAL PRICE

4. AUTHORITY *(Data Acquisition Document No.)* DI-NDTI-806441B
5. CONTRACT REFERENCE
6. REQUIRING OFFICE DEFENSE SUPPLY CENTER P

7. DD 250 REQ LT
8. APP CODE
9. DIST STATEMENT REQUIRED
10. FREQUENCY AS REQUIRED
11. AS OF DATE
12. DATE OF FIRST SUBMISSION BLOCK 16*
13. DATE OF SUBSEQUENT SUBMISSION

14. DISTRIBUTION

a. ADDRESSEE	b. COPIES Draft	Final Reg	Final Repro
CAO		1	
NAVAIR CP 3.3.2		1	
DSCR/VC		1	
15. TOTAL →		3	

16. REMARKS
ORIGINAL AND TWO COPIES

1. DATA ITEM NO. 0004
2. TITLE OF DATA ITEM REQUEST FOR WAIVER
3. SUBTITLE
17. PRICE GROUP
18. ESTIMATED TOTAL PRICE

4. AUTHORITY *(Data Acquisition Document No.)* DI-CMAN-80641B
5. CONTRACT REFERENCE
6. REQUIRING OFFICE DEFENSE SUPPLY CENTER P

7. DD 250 REQ LT
8. APP CODE
9. DIST STATEMENT REQUIRED
10. FREQUENCY AS REQUIRED
11. AS OF DATE
12. DATE OF FIRST SUBMISSION BLOCK 16*
13. DATE OF SUBSEQUENT SUBMISSION

14. DISTRIBUTION

a. ADDRESSEE	b. COPIES Draft	Final Reg	Final Repro
CAO		1	
NAVAIR CP 3.3.2		1	
DSCR/VC		1	
15. TOTAL →		3	

16. REMARKS
ORIGINAL AND TWO COPIES

G. PREPARED BY	H. DATE	I. APPROVED BY	J. DATE
Timothy L. Bennett Timothy L. Bennett	19 August 03	Adam Dost	10/10/03

DEPARTMENT OF THE NAVY
NAVAL AIR DEPOT
PSC BOX 8021
CHERRY POINT, NC 28533-0021

IN REPLY REFER TO

4408
Ser MMHISST.8-TLB/05429

2 6 NOV 2003

From: Commanding Officer
To: Commanding Officer, Naval Inventory Control Point (Code 734.12), 700 Robbins Avenue, Philadelphia PA 19111-5098

Subj: REQUEST FOR ENGINEERING SOURCE APPROVAL FOR ALTERNATE SOURCE QUALIFICATION (ASQ) TECHNICAL DATA PACKAGE (TDP) 05429, H60, BALL BEARING UNIT, P/N (78286) 70400-01612-044, NSN 3130-01-383-7605; AS FURNISHED BY A.F. MACHINE AND TOOL COMPANY INCORPORATED (64406)

Ref: (a) 339 DSCR-JA-03-05429 of 10 April 03
(b) ASQ Desktop Reference Manual for Technical Review for New Sources of Critical Safety Parts of 7 Apr 99
(c) NAVAIRINST 4200.25D

Encl: (1) ASQ TDP Technical Review Checklist
(2) ASQ TDP H60 05429
(3) Quality Assurance Provisions
(4) First Article Testing Requirements (Government Testing)
(5) First Article Approval (Government Testing)
(6) Production Lot Testing Requirements (Government Testing)
(7) Production Lot Testing (Government Testing)
(8) Contract Data Requirements List (CDRL)

1. Reference (a) requested that we perform a final engineering review per the requirements of references (b) and (c) on the subject ASQ TDP, forwarded as enclosure (1). A. F. Machine and Tool Company Incorporated of Inglewood, California has requested source approval under Category I on the basis of having previously manufactured the same part for Defense Logistics Agency (DLA). There is no record of an ASQ TDP being submitted by A. F. Machine and Tool Company Incorporated previously for the subject ball bearing unit.

2. Enclosure (1) identifies our findings/concerns resulting from a review of enclosure (2). The Quality Assurance Provisions, First Article Inspection, Production Lot Inspection and Contract Data Requirement Lists have been corrected and are forwarded as enclosures (3) through (8).

3. This ASQ TDP is conditionally accepted pending the inclusion of the following requirements:

Subj: REQUEST FOR ENGINEERING SOURCE APPROVAL FOR ALTERNATE SOURCE QUALIFICATION (ASQ) TECHNICAL DATA PACKAGE (TDP) 05429, H60, BALL BEARING UNIT, P/N (78286) 70400-01612-044, NSN 3130-01-383-7605; AS FURNISHED BY A.F. MACHINE AND TOOL COMPANY INCORPORATED (64406)

a. Members of the MMHISST.1 and ASQ Team prior to a contract award shall conduct a vendor survey.

b. A. F. Machine and Tool Company Incorporated shall only use Sikorsky approved sub-vendors.

c. Enclosures (3) through (8) shall be included in any resulting contract.

4. The point of contact for this ASQ TDP is Mr. Timothy L. Bennett (MMHISST.8), DSN 451-8968 or (252) 464-8968.

R. B. POLLOCK
By direction

Copy to:
COMNAVAIRSYSCOM Patuxent River MD (AIR-4.1C) (w/o encls)